



NOTES:

1. SEDIMENTS AND OTHER MATERIALS MAY NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONSTRUCTION ENTRANCE ROADWAYS MUST BE STABILIZED SO AS TO INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC WAY.
2. ACCIDENTAL DEPOSITIONS MUST BE SWEEPED UP IMMEDIATELY AND MAY NOT BE WASHED DOWN BY WATER, RAIN OR OTHER MEANS.
3. CONSTRUCTION ENTRANCE SHALL BE IN PLACE PRIOR TO LAND DISTURBANCE
4. CONSTRUCTION ENTRANCE SHALL BE IN PLACE FOR THE DURATION OF THE PROJECT
5. EITHER FIBER ROLLS OR SILT FENCING IS TO BE PLACED ALONG THE PROPERTY LINE UP TO BOTH SIDES OF THE ENTRANCE.
6. RESIDENTIAL CONSTRUCTION ENTRANCE SHALL BE CONSTRUCTED OF A 12" THICK LAYER OF 3" MINIMUM ROCK OVER FILTER FABRIC.
7. THIS DETAIL SHOWS MINIMUM REQUIREMENTS. IF BMP IS NOT FUNCTIONING PROPERLY THE CITY WILL REQUIRE ADDITIONAL MEASURES.
8. CONSTRUCTION ENTRANCE SHALL BE REMOVED WHEN PROJECT IS READY FOR FINAL INSPECTION.

DRAWN BY:	A.L.
APPROVED BY:	M.H.
DATE:	05/29/2020



City of Hesperia
RESIDENTIAL IN-FILL
CONSTRUCTION ENTRANCE

BE-1
BUILDING & SAFETY DIVISION